

City of Cumming Raw Water Intake Cumming, GA



PROJECT OVERVIEW AND CHALLENGES

The City of Cumming, GA constructed a new raw water intake in Lake Lanier. Bradshaw Construction was contracted to install the 66" steel casing pipe from the on shore pump station shaft to the intake structure at the bottom of the lake. The pump station shaft was constructed by the jet grout method. Bradshaw jacked the casing using a slurry microtunneling machine. The intake pipeline was designed as a "one-pass" system, there was no separate interior carrier pipe. The 66" steel casing pipe was lined & coated with epoxy based materials to withstand corrosion. The MTBM was recovered underwater by divers and hoisted to a barge.



PROJECT INFORMATION - 465

OWNER:

City of Cumming, GA
Franklin Wagner
770-205-4220

ENGINEER:

Civil Engineering Consultants
Butch Johnson
770-977-5747

CONTRACTOR:

W. L. Hailey

COMPLETION DATE:

6/30/2008

GEOLOGY:

Piedmont residual soils

EXCAVATION METHOD:

Herrenknecht AVN-1200 MTBM

MINING DIMENSIONS:

350' x 66" Ø

FINAL LINING:

66" Steel Casing (lined & coated)

FOR MORE INFORMATION:

Todd Brown, Project Manager
410-970-8300
tbrown@bradshawcc.com
Refer to Project 465